

PPN # 205414—BID 37484

TO BE PUBLISHED ONE TIME ON JUNE 25, 2014

SEALED PROPOSALS

Notice is hereby given that bids will be received at the office of the Purchasing Manager, up to 10:00 a.m., Friday, July 11, 2014 for the following project:

135th St West, Maple to Central Paving Improvements
472-84308

LUMP SUM BID ITEMS

Field Office & Lab (Type A)	1	LS
Mobilization	1	LS
Site Clearing	1	LS
Site Restoration	1	LS
Fence Rem'd	1	LS
Removal of Existing Structures	1	LS
Transportation of Salvaged Material	1	LS
Excavation	27,058	cy
Fill, Compacted (95% Density)	1,829	cy
Fill, Loose	2,858	cy
Grading, Ditch	1	LS
Pavement &/or Curb Rem'd	15,184	sy
Concr. Driveway Rem'd	730	sy
Concr. Sidewalk Rem'd	118	sy
Concr. Flume Removed	98	lf
AC Pvm't 5" (3" Base)	751	sy
AC Pvm't 7" (5" Base)	18,917	sy
Concrete Pvm't (VG) 8" Reinf.	1,130	sy
Concr. C & G Type 1 (6" & 1 1/2")	8,781	lf
Concr. C & G Type 2 (6" & 1 1/2")	201	lf
Concr. C & G Type 3 (8" & 1 1/2")	706	lf
Concr. C & G Type 4 (6 5/8" & 1 1/2")	330	lf
Concr. C+G, Mono Edge (6" & 1 1/2")	605	lf
Concr. Ramp Nose Section (Median)	7	ea
Crushed Rock Base 5", Reinf	790	sy
Crushed Rock Base 7", Reinf	1,621	sy
Crushed Rock Base 8", Reinf	22,605	sy
WCR w/ Det Warn	13	ea
Handrail	112	lf
MH Adjusted, SS	4	ea

LUMP SUM BID ITEMS - Drainage

Pipe, SWS, RCP 15"	2,044	lf
Pipe, SWS, RCP 18"	496	lf
Pipe, SWS, RCP 24"	337	lf
Pipe, SWS, RCP 30"	178	lf
Pipe, SWS, RCP 36"	682	lf
Pipe, SWS, RCP 48"	44	lf
Pipe, SWS, HERCP (29" x 45")(36")	239	lf
Pipe, SWS, HERCP (34" x 53")(42")	458	lf

Pipe, SWS, RCBC (5' x 3')	296	lf
Pipe, SWS, RCBC (3 - 8' x 5')	56	lf
Wingwalls	4	ea
Pipe, End Section (15")	1	ea
Pipe, End Section (18")	1	ea
Pipe, End Section (36")	1	ea
Pipe, End Section (48")	1	ea
Pipe, End Section (34" x 53")	1	ea
Inlet, Curb (Type 1A)(L=10' W=3')	5	ea
Inlet, Curb (Type 1A)(L=10' W=4')	1	ea
Inlet, Curb (Type 1A)(L=10' W=5')	5	ea
Inlet, Curb (Type 1A)(L=10' W=6')	3	ea
Inlet, Curb (Type 1A)(L=15' W=3')	5	ea
Inlet, Curb (Type 1A)(L=5' W=5')	1	ea
Inlet, Curb (Type 1A)(L=5' W=3')	17	ea
Inlet, Curb (Type 1A)(L=5' W=7.5')	1	ea
Inlet, Drop (Double)	1	ea
Inlet Hookup	38	ea
MH, Connect to Existing	2	ea
MH, Shallow (Dia.= 4')	1	ea
MH, Standard (Dia. = 4')	1	ea
MH, Standard (Dia. = 8')	2	ea
MH, Reinf Concr. (L = 7.5', W = 3')	1	ea
MH, Reinf Concr. (L = 6', W = 5')	1	ea
MH, Water Quality (5')	1	ea
MH, Water Quality (7')	2	ea
MH, Water Quality (8')	1	ea
Rip Rap, Light Stone	168	sy
Sidewalk Flume	4	ea
Concrete Flume	10	lf
Ditch Liner	884	sy
Pipe Support Crossing	1	ea
LUMP SUM BID ITEMS - Traffic		
Pavement Marking	1	LS
Signing, Except Street Name Signs	1	LS
Signing, Street Name Signs Only	1	LS
Traffic Control	1	LS
LUMP SUM BID ITEMS - Landscaping		
Seeding	1	LS
Sodding	1	LS
MEASURED QTY BID ITEMS - Paving		
Concr. Driveway 8"	957	sf
Concr. Sidewalk 6"	1,574	sf
Concr. Sidewalk 4"	27,924	sf
Concr. Sidewalk 5"	44,190	sf
Concr. Sidewalk Protection Curb	170	lf
Retaining Wall (Block)	620	lf
Retaining Wall (Gravity)	67	lf
AC Pvmt (Temp)	300	sy
Concr. Pvmt 6"	125	sf

Sleeves, 4" PVC	256	lf
Sleeves, 6" PVC	140	lf
MEASURED QTY BID ITEMS - Water		
Valve Box Adj	17	ea
Water Meter Adj	1	ea
Fire Hydrant Adj	4	ea
MEASURED QTY BID ITEMS - Drainage		
Removed Pipe	730	lf
Pipe, Abandoned in Place	435	lf
Pipe, SWS, PVC 4", Perforated (Underdrain)	420	lf
Fill, Sand (Flushed & Vibrated)	4,770	lf
MEASURED QTY BID ITEMS - Erosion Control		
BMP, Back of Curb Protection	1,125	lf
BMP, Construction Entrance	6	ea
BMP, Curb Inlet Protection	34	ea
BMP, Ditch Check	9	ea
BMP, Drop Inlet Protection	2	ea
BMP, Silt Fence	5,800	lf
BMP, Erosion Control Mat	5,801	sy
MEASURED QTY BID ITEMS - Traffic Control		
Signing, Elec. Portable Message (each per day)	180	day
MEASURED QTY BID ITEMS - Landscaping		
Queen Elizabeth Maple (2 - 2 1/2" caliper)	4	ea
Shantung Maple (2 - 2 1/2" caliper)	12	ea
Trident Maple (2 - 2 1/2" caliper)	7	ea
Urbanite Ash (2 - 2 1/2" caliper)	8	ea
Thornless Cockspur Hawthorn (1 1/2 - 2" caliper)	13	ea
Oklahoma Redbud (1 1/2 - 2" caliper)	20	ea
Canada Red Chokecherry (1 1/2 - 2" caliper)	17	ea
Prairiefire Crab (1 1/2 - 2" caliper)	29	ea
Snow Drift Crab (1 1/2 - 2" caliper)	53	ea
Vanderwolf Limber Pine (5 - 6' height)	5	ea
Chinese Juniper (5 - 6' height)	9	ea
Trees, Sm Rem'd	19	ea
Trees, Lrg Rem'd	52	ea
Gate Removal, Sta 121+30 Lt.	1	ea
Gate Reset, Sta 121+30 Lt.	1	ea

All bids received will thereafter be publicly opened, read aloud and considered by the Board of Bids and Contracts. All work to be done under the direction and supervision of the City Manager and according to plans and specifications on file in the office of the City Engineer. Bidders will be required to enclose a bid bond in the amount of five per cent (5%) with each as a guarantee of good faith. The Wichita City Council reserves the right to reject any and all bids.

Dated at Wichita, Kansas, June 20, 2014.

Karen Sublett, City Clerk

This information and any addenda is also available on the City's Web Page at:
<http://ep.wichita.gov/>