

TO BE PUBLISHED ONE TIME ON JULY 17, 2013

## SEALED PROPOSALS

Notice is hereby given that bids will be received at the office of the Purchasing Manager, up to 10:00 a.m., Friday, August 23, 2013 for the following project:

**135th, Kellogg to Onewood**

(135th, north of Kellogg)

87N-0566-01/472-84915

**Lump Sum Bid Items - Paving (707022)**

Mobilization	1	LS
Mobilization (DBE)	1	LS
Field Off & Lab (Type A)	1	ea
Site Clearing	1	LS
Site Restoration	1	LS
Rem of Existing Structures	1	LS
Concr &/or Asphalt Pvmnt Rem	6,183	sy
Concr Sidewalk Rem	19	sy
Excavation	5,926	cy
Excavation, Borrow (Contractor Furnished)	1,060	cy
Fill, Compacted (95% Density)	5,678	cy
AC Pvmnt 7" (5" Bit Base) (BM-2)	8,479	sy
Crushed Rock Base 8", Reinf	10,133	sy
Concr C&G, Comb Type I (6" & 1-1/2")	4,251	lf
Wheelchair Ramp w/Det Warn	1	ea
Signing	1	LS
Pvmnt Marking	1	LS
Traffic Control	1	LS

**Lump Sum Bid Items - Drainage (707022)**

Inlet, Curb (Type 1) (L=5' W=3')	4	ea
Inlet, Curb (Type 1) (L=10' W=3')	13	ea
Inlet, Curb (Type 1) (L=10' W=4')	2	ea
Inlet Hookup	19	ea
MH, Reinf Concr (4' x 4')	2	ea
Pipe, PVC 4", Perforated (Inlet Underdrain)	209	lf
Pipe, SWS 15"	400	lf
Pipe, SWS 15" (RCP)	781	lf
Pipe, SWS 18"	375	lf
Pipe, SWS 18" (RCP)	44	lf
Pipe, SWS 24" (RCP)	87	lf
Pipe, SWS 30" (RCP)	53	lf
Pipe, Entrance 15"	72	lf
Pipe, 15" End Section	4	ea
Pipe, RCBC (2-10' x 6') w/ Wingwalls (Sta. 220+25)	106	lf
Handrail (Steel), Pedestrian (3'-6") (Sta. 220+25)	104	lf
Pipe, RCBC (4' x 3') w/ Wingwalls (Sta. 226+05)	91	lf
Handrail (Steel), Pedestrian (3'-6") (Sta. 226+05)	49	lf
Fill, Sand (Flushed & Vibrated)	1,161	lf

**Lump Sum Bid Items - Landscaping (707022)**

Seeding	1	LS
Sodding, Fescue	1	LS

**Measured Qty Bid Items - Paving (707022)**

Concr Sidewalk 4"	12,866	sf
Concr Sidewalk 5"	22,098	sf
Concr Sidewalk Protection Curb	70	lf
Concr Driveway 8" (Reinf)	5,546	sf
Surfacing Material 2" (SA-1) (Driveway)	1,300	sf
AC Pvmnt 6" (4" Bit Base), Temp for Widening (w/5" Crushed Rock Base)	354	sy
AC Pvmnt 6", Temp for Patching	117	sy
Riprap, Light Stone	393	sy
Sign, Electronic Portable Message	50	day

**Measured Qty Bid Items - Erosion Control BMP (707022)**

BMP, Curb Inlet Protection	19	ea
BMP, Silt Fence	4,250	lf
BMP, Construction Entrance	2	ea
BMP, Back of Curb Protection	4,081	lf

**Measured Qty Bid Items - Landscaping (707022)**

Tree, Japanese Tree Lilac-2.5" caliper	12	ea
Tree, Oklahoma Redbud-2.5" caliper	14	ea
Tree, Professor Sprenger Crabapple-2.5" caliper	20	ea
Tree, Zumi Crabapple-2.5" caliper	16	ea
Tree, Goldenraintree-2.5" caliper	7	ea
Tree, Hedge Maple-2.5" caliper	7	ea
Tree, Chinquapin Oak-3" caliper	13	ea

**Water Improvements (Non-Participating)****Measured Qty Bid Items (635813)**

Pipe, WL 16"	1,778	lf
Pipe, DICL RJ 16"	113	lf
Pipe, DICL SJ 16"	48	lf
Valve Assembly, Anchored, 16"	2	ea
Valve Assembly, 16"	1	ea
Fire Hydrant Assembly	4	ea
Fill, Sand (Flushed & Vibrated)	82	lf
Conc. Pvmnt. Rem. - Asph. Repl.	30	lf
Concrete Driveway Rem & Repl	30	lf
Gravel Streets/Drives Rem & Repl	41	lf
BMP, Silt Fence	346	lf

All bids received will thereafter be publicly opened, read aloud and considered by the Board of Bids and Contracts. All work to be done under the direction and supervision of the City Manager and according to plans and specifications on file in the office of the City Engineer. Bidders will be required to enclose a bid bond in the amount of five per cent (5%) with each as a guarantee of good faith. The Wichita City Council reserves the right to reject any and all bids.

Dated at Wichita, Kansas, June 27, 2013.

Karen Sublett, City Clerk

This information and any addenda is also available on the City's Web Page at:  
<http://ep.wichita.gov/>