

TO BE PUBLISHED ONE TIME ON AUGUST 12, 2015

## SEALED PROPOSALS

Notice is hereby given that bids will be received at the office of the Purchasing Manager, up to 10:00 a.m., Friday, September 11, 2015 for the following project:

**21st St Bridge at Derby Refinery**

(21st, west of I-135)

87N-0612-01/472-85120

**Lump Sum Bid Items - Paving (715732)**

Field Office and Laboratory (Type A)	1	LS
Site Clearing	1	LS
Mobilization	1	LS
Transport of Salvaged Materials (Non-Part)	1	LS
Pvmt &/or Curb Rem	1,324	sy
Removal of Existing Structures	1	LS
Shoring, Temp	1	LS
Construction Staking	1	LS
Concr Pavement 12" (Reinf.)	317	sy
Concr Approach 12", Bridge	324	sy
Concr Safety Barrier, Special	101	lf
Bridge Approach Slab Footing	42	cy
AC Pvmt 7" (5" Bit. Base)	369	sy
Crushed Rock Base 6", Reinf	699	sy
Crushed Rock Base 8", Reinf	418	sy
Concr C&G, Type 1, Special (6" & 1-1/2")	361	lf
Concr Sidewalk 12" (Reinf.)	139	sf
Pipe, SWS 18" RCP	58	lf
Pipe, SWS 24" RCP	110	lf
Pipe, SWS 30" RCP	116	lf
Inlet, Curb (Type 1)(L=10' W=4')	3	ea
Inlet, Curb (Type 2)(L=6' 2-1/2" W=3' 4-3/8")	2	ea
Inlet, Grated Driveway, Double	1	ea
MH, Reinf Concrete (5' x 5')	1	ea
Inlet Hookup	6	ea
Inlet Removed	4	ea
Sodding	1	LS
Site Restoration	1	LS

**Lump Sum Bid Items - Bridge (715732)**

Cast Steel Pile Points	16	ea
Structural Steel (M270)(Gr 50WT3)	105,326	lbs
Structural Steel (A709)(Gr 50WT3)	28,726	lbs
Structural Steel (A709)(Gr 50W)	2,556	lbs
Welded Stud Shear Connectors	2,352	ea
Reinf Steel (Grade 60)(Epoxy Coated)	34,120	lbs
Bridge Deck Strip Seal	53	lf
Concrete (Grade 4.0)(AE)	38	cy
Concrete (Grade 4.0)(AE)(SA)	138	cy
Bridge Deck Grooving	272	sy
Pipe Hanger Assembly	5	ea
Bridge Plaque (Non-Part)	1	ea
Curing Environment	1	LS

**Lump Sum Bid Items - Traffic (715732)**

Pavement Markings	1	LS
Sign, Existing, Rem	2	ea
Traffic Control	1	LS
Junction Box	1	ea
Detector Loop Installation	1	LS

**Measured Qty Bid Items - Paving (715732)**

Sidewalk, Drive, &/or Pkg Lot Rem	140	sy
Excavation, Special Waste	912	cy
Excavation, Hazardous Waste	50	cy
Excavation, Contractor Furnished	220	cy
Concrete Driveway 8"	38	sf
Concrete Sidewalk 4"	298	sf
Sidewalk Thickening	90	lf
Concrete Sidewalk Protection Curb	40	lf
Rip-Rap, Reinf Concrete 6"	27	sy
Retaining Wall, Reinf	48	sf-face
Pipe, SWS 4", PVC, Perforated	40	lf
Fill, Sand (Flushed and Vibrated)	374	lf
Pipe Removed	114	lf

**Measured Qty Bid Items - Paving (715732)**

Piles (Steel) (HP14x83)	497	lf
Contractor Furnished PDA	2	ea

**Measured Qty Bid Items - Erosion Control BMP (715732)**

BMP, Back of Curb Protection	133	lf
BMP, Construction Entrance	4	ea
BMP, Curb Inlet Protection	4	ea
BMP, Silt Fence	156	lf

**Measured Qty Bid Items - Landscaping (715732)**

Signing, Elec. Port. Message (each per day)	60	day
Concr Safety Barrier, Temp	552	lf

**Water Improvements (Non-Part)****Measured Qty Bid Items (636309)**

Pipe, WL 8"	41	lf
Pipe, WL 8", DICL	3	lf
Valve Assembly, Anchored 8"	1	ea
Valve Assembly, Blowoff 2"	2	ea
Pipe, Cut and Cap 8"	2	ea
Pvmt &/or Curb Rem and Repl	10	sy

All bids received will thereafter be publicly opened, read aloud and considered by the Board of Bids and Contracts. All work to be done under the direction and supervision of the City Manager and according to plans and specifications on file in the office of the City Engineer. Bidders will be required to enclose a bid bond in the amount of five per cent (5%) with each as a guarantee of good faith. The Wichita City Council reserves the right to reject any and all bids.

Dated at Wichita, Kansas, August 4, 2015.

Karen Sublett, City Clerk

This information and any addenda is also available on the City's Web Page at:  
<http://ep.wichita.gov/>