



# BID BULLETIN



## Upcoming Projects from Public Works–Engineering

### General Information

The City of Wichita receives bids at the Purchasing office (455 N.Main, 12th Floor) up to 10:00 a.m. on the Friday specified for each project in this bulletin. All bids received online and/or on paper will thereafter be publicly opened, read aloud, and considered by the Board of Bids and by City Council. The Wichita City Council reserves the right to reject any and all bids.

Plans & Specifications for these projects are generally available 10 days prior to the bid date unless otherwise specified. All work is to be done under direction and supervision of the City Manager and according to the plans & specifications on file in the City Engineer's Office. Bidders are required to include a bid bond in the amount of five percent (5%) with each bid.

Requests for the bid documents & plans should be directed to QuikPrint (942-2208). Other questions should be directed to the project Engineer (268-4501).

The successful bidder may contact Kim Pelton (268-4499) for extra sets of plans/specs.

**NOTE: All information contained herein is subject to change.**

### PAV/PAV/SWD PROJECT

#### 34th Street North (now Silver Fox)

472-85166 490338

#### Maize Turn Lane - Phase 1

472-85167 490358

#### Stormwater Drain #394

468-84953 485425

#### Fox Ridge Plaza Addition

**Bid Date: 08-07-15; Award Date: 08-11-15**

#### LUMP SUM BID ITEMS - Group 1 (766317)

Crushed Rock Base 6", Reinforced	8,453	sy
Concrete Pavement (VG) 7" (Reinf)	727	sy
Concrete C & G, Type 3 (8"), Median	2,041	lf
Concrete C & G, Type 4 (6-5/8"), City	2,490	lf
Concrete Curb, Mono Edge (6-5/8")	202	lf
Concrete Sidewalk 4"	7,118	sf
Wheelchair Ramp w/ Det Warn	6	ea
AC Pavement 4" - Bike Path	1,440	sf
Inlet Hookup	6	ea
Inlet Adjusted	6	ea
Sleeves, 6" PVC	462	lf
Traffic Control	1	LS
Traffic Signal Conduit	90	lf
Signing	1	LS
Site Clearing	1	LS
Site Restoration	1	LS

#### MEASURED QTY BID ITEMS - Group 1 (766317)

Valve Box Adjusted	1	ea
Pavement Removed	5,305	sy
Pavement Underdrain	90	lf

#### OPTION #1 BID ITEMS

#### (Asphalt Alternative) - Group 1 (766317)

AC Pavement 6" (4" Bit Base)	5,915	sy
------------------------------	-------	----

#### OPTION #2 BID ITEMS

#### (Concrete Alternative) - Group 1 (766317)

Concrete Pavement, 7"	5,915	sy
-----------------------	-------	----

#### ADD ALTERNATE #1 BID ITEMS

#### (Construction Sequencing) - Group 1 (766317)

AC Pvmnt 6" (4" Bit Base)(Temp)	646	sy
Pavement Removed	646	sy
Traffic Control	1	LS

#### LUMP SUM BID ITEMS - Group 2 (766337)

Crushed Rock Base 6", Reinforced	450	sy
Concrete Pavement (VG) 7" (Reinf)	441	sy
Concrete Curb, Mono Edge (6-5/8")	72	lf

Continued in Next Column

July 23, 2015

#### 34th Street North (now Silver Fox)

#### Maize Turn Lane - Phase 1

#### Stormwater Drain #394

#### Fox Ridge Plaza Addition

**Bid Date: 08-07-15; Award Date: 08-11-15**

#### LUMP SUM BID ITEMS - Group 2 (766337)

Continued

AC Pavement 4" - Bike Path	1,473	sf
Pipe, SWS, HERCP (24"x38") {30}	329	lf
Ditch Liner	33	sy
Site Clearing	1	LS

#### LUMP SUM BID ITEMS - Group 3 (751534)

Excavation	61,500	cy
Fill, Compacted (95% Density)	40,160	cy
Fill, Compacted (95% Density)-Clay Liner	9,040	cy
Plug - Wetland Plugs	2,000	ea
Seeding - Wet Prairie Mix	6	ac
Seeding - Slope Mix	8	ac
Seeding - Cover Crop & Mulching	25	ac
Ditch Liner	32	sy
Site Clearing	1	LS
Site Restoration	1	LS

#### MEASURED QTY BID ITEMS - Group 3 (751534)

BMP, Construction Entrance	1	ea
BMP, Curb Inlet Protection	16	LS
BMP, Silt Fence	2,370	lf
BMP, Back of Curb Protection	2,830	lf

\*\*\*\*\*

Page 1 of 1

A minority/women-owned business is 51% owned and controlled by a minority or women. MBE/DBE classes are defined as: Asian (A) American Indian (AI) Black (B) Hispanic (H) and Women-owned (WO). We appreciate your cooperation in providing this information.