



BID BULLETIN



Upcoming Projects from Public Works–Engineering

General Information

The City of Wichita receives bids at the Purchasing office (455 N.Main, 12th Floor) up to 10:00 a.m. on the Friday specified for each project in this bulletin. All bids received online and/or on paper will thereafter be publicly opened, read aloud, and considered by the Board of Bids and by City Council. The Wichita City Council reserves the right to reject any and all bids.

Plans & Specifications for these projects are generally available 10 days prior to the bid date unless otherwise specified. All work is to be done under direction and supervision of the City Manager and according to the plans & specifications on file in the City Engineer's Office. Bidders are required to include a bid bond in the amount of five percent (5%) with each bid.

Requests for the bid documents & plans should be directed to QuikPrint (942-2208).

Other questions should be directed to the project Engineer (268-4501).

The successful bidder may contact Kim Pelton (268-4499) for extra sets of plans/specs.

NOTE: All information contained herein is subject to change.

KDOT PAVING PROJECT

August 4, 2015

21st Street Bridge at Derby Refinery (21st, west of I-135)

87N-0612-01/472-85120

Bid Date: 08-23-13; Award Date: Pending KDOT Approval

Lump Sum Bid Items - Paving (715732)

Field Office and Laboratory (Type A)	1	LS
Site Clearing	1	LS
Mobilization	1	LS
Transport of Salvaged Materials (Non-Participating)	1	LS
Pavement &/or Curb Removed	1,324	sy
Removal of Existing Structures	1	LS
Shoring, Temporary	1	LS
Construction Staking	1	LS
Concrete Pavement 12" (Reinf.)	317	sy
Concrete Approach 12", Bridge	324	sy
Concrete Safety Barrier, Special	101	lf
Bridge Approach Slab Footing	42	cy
AC Pavement 7" (5" Bit. Base)	369	sy
Crushed Rock Base 6", Reinforced	699	sy
Crushed Rock Base 8", Reinforced	418	sy
Concrete C & G, Type 1, Special (6" & 1-1/2")	361	lf
Concrete Sidewalk 12" (Reinf.)	139	sf
Pipe, SWS 18" RCP	58	lf
Pipe, SWS 24" RCP	110	lf
Pipe, SWS 30" RCP	116	lf
Inlet, Curb (Type 1)(L=10' W=4')	3	ea
Inlet, Curb (Type 2)(L=6' 2-1/2" W=3' 4-3/8")	2	ea
Inlet, Grated Driveway, Double	1	ea
MH, Reinforced Concrete (5' x 5')	1	ea
Inlet Hookup	6	ea
Inlet Removed	4	ea
Sodding	1	LS
Site Restoration	1	LS

Lump Sum Bid Items - Bridge (715732)

Cast Steel Pile Points	16	ea
Structural Steel (M270) (Gr 50WT3)	105,326	lbs
Structural Steel (A709) (Gr 50WT3)	28,726	lbs
Structural Steel (A709) (Gr 50W)	2,556	lbs
Welded Stud Shear Connectors	2,352	ea
Reinforcing Steel (Grade 60) (Epoxy Coated)	34,120	lbs
Bridge Deck Strip Seal	53	lf
Concrete (Grade 4.0)(AE)	38	cy
Concrete (Grade 4.0)(AE)(SA)	138	cy
Bridge Deck Grooving	272	sy

Continued on next page

Page 1 of 2

A minority/women-owned business is 51% owned and controlled by a minority or women. MBE/DBE classes are defined as: Asian (A) American Indian (AI) Black (B) Hispanic (H) and Women-owned (WO). We appreciate your cooperation in providing this information.



BID BULLETIN



Upcoming Projects from Public Works–Engineering

General Information

The City of Wichita receives bids at the Purchasing office (455 N.Main, 12th Floor) up to 10:00 a.m. on the Friday specified for each project in this bulletin. All bids received online and/or on paper will thereafter be publicly opened, read aloud, and considered by the Board of Bids and by City Council. The Wichita City Council reserves the right to reject any and all bids.

Plans & Specifications for these projects are generally available 10 days prior to the bid date unless otherwise specified. All work is to be done under direction and supervision of the City Manager and according to the plans & specifications on file in the City Engineer's Office. Bidders are required to include a bid bond in the amount of five percent (5%) with each bid.

Requests for the bid documents & plans should be directed to QuikPrint (942-2208). Other questions should be directed to the project Engineer (268-4501).

The successful bidder may contact Kim Pelton (268-4499) for extra sets of plans/specs.

NOTE: All information contained herein is subject to change.

August 4, 2015

KDOT PAVING PROJECT Continued

21st Street Bridge at Derby Refinery

87N-0612-01/472-85120

Lump Sum Bid Items - Bridge (715732) Continued

Pipe Hanger Assembly	5	ea
Bridge Plaque (Non-Participating)	1	ea
Curing Environment	1	LS

Lump Sum Bid Items - Traffic(715732)

Pavement Markings	1	LS
Sign, Existing, Removed	2	ea
Traffic Control	1	LS
Junction Box	1	ea
Detector Loop Installation	1	LS

Measured Qty Bid Items - Paving (715732)

Sidewalk, Drive, &/or Pkg Lot Removed	140	sy
Excavation, Special Waste	912	cy
Excavation, Hazardous Waste	50	cy
Excavation, Contractor Furnished	220	cy
Concrete Driveway 8"	38	sf
Concrete Sidewalk 4"	298	sf
Sidewalk Thickening	90	lf
Concrete Sidewalk Protection Curb	40	lf
Rip-Rap, Reinforced Concrete 6"	27	sy
Retaining Wall, Reinforced	48	sf-face
Pipe, SWS 4", PVC, Perforated	40	lf
Fill, Sand (Flushed and Vibrated)	374	lf
Pipe Removed	114	lf

Measured Qty Bid Items - Paving (715732)

Piles (Steel) (HP14x83)	497	lf
Contractor Furnished PDA	2	ea

Measured Qty Bid Items - Erosion Control BMP (715732)

BMP, Back of Curb Protection	133	lf
BMP, Construction Entrance	4	ea
BMP, Curb Inlet Protection	4	ea
BMP, Silt Fence	156	lf

Measured Qty Bid Items - Landscaping (715732)

Signing, Elec. Portable Message (each per day)	60	day
Concrete Safety Barrier, Temporary	552	lf

Water Improvements (Non-Participating)

Measured Qty Bid Items (636309)

Pipe, WL 8"	41	lf
Pipe, WL 8", DICL	3	lf
Valve Assembly, Anchored 8"	1	ea
Valve Assembly, Blowoff 2"	2	ea
Pipe, Cut and Cap 8"	2	ea
Pavement &/or Curb Removed and Replaced	10	sy

Page 2 of 2

A minority/women-owned business is 51% owned and controlled by a minority or women. MBE/DBE classes are defined as: Asian (A) American Indian (AI) Black (B) Hispanic (H) and Women-owned (WO). We appreciate your cooperation in providing this information.