



BID BULLETIN



Upcoming Projects from Public Works–Engineering

General Information

The City of Wichita receives bids at the Purchasing office (455 N.Main, 12th Floor) up to 10:00 a.m. on the Friday specified for each project in this bulletin. All bids received online and/or on paper will thereafter be publicly opened, read aloud, and considered by the Board of Bids and by City Council. The Wichita City Council reserves the right to reject any and all bids.

Plans & Specifications for these projects are generally available 10 days prior to the bid date unless otherwise specified. All work is to be done under direction and supervision of the City Manager and according to the plans & specifications on file in the City Engineer's Office. Bidders are required to include a bid bond in the amount of five percent (5%) with each bid.

Requests for the bid documents & plans should be directed to QuikPrint (942-2208). Other questions should be directed to the project Engineer (268-4501).

The successful bidder may contact Kim Pelton (268-4499) for extra sets of plans/specs.

NOTE: All information contained herein is subject to change.

PAVING PROJECT

April 15, 2014

Mt. Vernon & Oliver Intersection Improvements (Mt. Vernon & Oliver Intersection)

87N-0548-01/472-85042 211502/ 774071

Bid Date: 05-30-14; Award Date: Upon KDOT Approval

LUMP SUM BID ITEMS (707037)

Field Office & Laboratory (Type A)	1	LS
Mobilization	1	LS
Mobilization (DBE)	1	LS
Site Clearing	1	LS
Site Restoration	1	LS
Removal of Existing Structure	1	LS
Concrete &/or Asphalt Pavement Rem'd	7,589	sy
Concrete &/or Asph. Sdwk, Dr, &/or Pkg Lot Rem'd	3,059	sy
Excavation	2,535	cy
Fill, Compacted (95% Density)	122	cy
Concrete Pavement 9" (Reinf)	1,458	sy
Concrete Pavement 9" (NRDJ)	7,073	sy
Concrete Pavement (VG) 8" (Reinf)	236	sy
Crushed Rock Base 7", Reinf	189	sy
Crushed Rock Base 6", Reinf	9,512	sy
Concrete C & G, Comb. Type 1 (6" & 1-1/2")	2,775	lf
Concrete Curb, Mono Edge (6" & 1-1/2")	145	lf
Brick Pavers (Concrete), Crosswalk	249	sy
Wheelchair Ramp w/ Detectable Warnings	15	ea
Valve Box Adjusted	4	ea
AT&T Manholes Adjusted	2	ea
Remove, Protect and Reset Bus Bench 7 Bicycle Racks	1	LS
Sodding, Bermuda	1	LS

MEASURED QUANTITY BID ITEMS (707037)

Concrete Driveway 8" (Reinf)	15,975	sf
Concrete Pavement 6" (Reinf)(Pkg Lot)	326	sf
AC Pavement 6" (4" Bit Base)(Pkg Lot)	254	sy
Concrete Sidewalk 4"	4,930	sf
Concrete Sidewalk 5"	5,644	sf
Concrete Protection Curb	60	lf
Signing, Arrow Board (each per day)	30	DY

LUMP SUM BID ITEMS - Traffic (707037)

Pavement Marking	1	LS
Signing	1	LS
Traffic Control	1	LS
Traffic Signalization	1	LS
Traffic Signalization, Temporary	1	LS

Continued on next page

Page 1 of 2

A minority/women-owned business is 51% owned and controlled by a minority or women. MBE/DBE classes are defined as: Asian (A) American Indian (AI) Black (B) Hispanic (H) and Women-owned (WO). We appreciate your cooperation in providing this information.



BID BULLETIN



Upcoming Projects from Public Works–Engineering

General Information

The City of Wichita receives bids at the Purchasing office (455 N.Main, 12th Floor) up to 10:00 a.m. on the Friday specified for each project in this bulletin. All bids received online and/or on paper will thereafter be publicly opened, read aloud, and considered by the Board of Bids and by City Council. The Wichita City Council reserves the right to reject any and all bids.

Plans & Specifications for these projects are generally available 10 days prior to the bid date unless otherwise specified. All work is to be done under direction and supervision of the City Manager and according to the plans & specifications on file in the City Engineer's Office. Bidders are required to include a bid bond in the amount of five percent (5%) with each bid.

Requests for the bid documents & plans should be directed to QuikPrint (942-2208). Other questions should be directed to the project Engineer (268-4501).

The successful bidder may contact Kim Pelton (268-4499) for extra sets of plans/specs.

April 15, 2014

PAVING PROJECT

Mt. Vernon & Oliver Intersection Improvements (Mt. Vernon & Oliver Intersection)

87N-0548-01/472-85042 211502/ 774071

CONTINUED

LUMP SUM BID ITEMS - Non-Participating (707037)

Transportation of Salvaged Materials	1	LS
Project Signage (D-3 Metro Street Name Signs)	1	LS

MEASURED QUANTITY BID ITEMS - Erosion Control BMP (707037)

BMP, Back of Curb Protection	1,951	lf
------------------------------	-------	----

MEASURED QUANTITY BID ITEMS (636302)

Water Improvements (Non-Participating)

Fire Hydrant Assembly	1	ea
Fire Hydrant w/o Valve	1	ea
Pipe, WL 12"	118	lf
Pipe, WL 8"	1,125	lf
Pipe, WL 2 1/2"	50	lf
Pipe, WL 2"	20	lf
Pipe, DICI 8"	78	lf
Pipe, DICI 6"	71	lf
Pipe, DICI 2"	3	lf
Valve Assembly, Anchored 12"	1	ea
Valve Assembly, Anchored 8"	5	ea
Valve Assembly, Anchored 6"	1	ea
Valve Assembly, Gate 8"	1	ea
Valve Assembly, Blowoff 2"	1	ea
Service Outlet Assembly, 2"	1	ea
Service Line Short, 2"	1	ea
Service Line Long, 1"	8	ea
Service Line Short, 1"	6	ea
Fire Hydrant Removal	2	ea
Valve Assemblies Abandoned	11	ea
Valve Assemblies Removed	1	ea
Water Meter Adjusted	3	ea
Concrete &/or Asphalt Pavement Rem'd	610	sy
AC Patch (Comm. Grade), Temp.	610	sy
Fill, Sand (Flushed & Vibrated)	1,367	lf

NOTE: All information contained herein is subject to change.

A minority/women-owned business is 51% owned and controlled by a minority or women. MBE/DBE classes are defined as: Asian (A) American Indian (AI) Black (B) Hispanic (H) and Women-owned (WO). We appreciate your cooperation in providing this information.