



# BID BULLETIN



## Upcoming Projects from Public Works–Engineering

### General Information

The City of Wichita receives bids at the Purchasing office (455 N.Main, 12th Floor) up to 10:00 a.m. on the Friday specified for each project in this bulletin. All bids received online and/or on paper will thereafter be publicly opened, read aloud, and considered by the Board of Bids and by City Council. The Wichita City Council reserves the right to reject any and all bids.

Plans & Specifications for these projects are generally available 10 days prior to the bid date unless otherwise specified. All work is to be done under direction and supervision of the City Manager and according to the plans & specifications on file in the City Engineer's Office. Bidders are required to include a bid bond in the amount of five percent (5%) with each bid.

Requests for the bid documents & plans should be directed to QuikPrint (942-2208). Other questions should be directed to the project Engineer (268-4501).

The successful bidder may contact Kim Pelton (268-4499) for extra sets of plans/specs.

**NOTE: All information contained herein is subject to change.**

June 5, 2014

### WATER PROJECT

#### Water Distribution System

##### The Ranch Addition

448-90618 470172

**Bid Date: 06-20-14; Award Date: 06-24-14**

#### **LUMP SUM BID ITEMS**

Pipe, WL 6"	351	lf
Pipe, WL 8"	1,699	lf
Fire Hydrant Assembly	5	ea
Valve Assembly, Blowoff 2"	2	ea
Valve Assembly, 8"	2	ea
Valve Assembly, Anchored 8", Special	1	ea
Maintain Existing BMPs	1	LS
Seeding	1	LS
Site Clearing	1	LS
Site Restoration	1	LS

\*\*\*\*\*

### SEWER PROJECT

#### Lateral 437, Four Mile Creek Sewer

##### The Ranch Addition

468-84919 480053

**Bid Date: 06-20-14; Award Date: 06-24-14**

#### **LUMP SUM BID ITEMS**

Pipe, SS 8"	3,485	lf
Air Testing, SS Pipe	3,535	lf
MH, Standard SS (4')	7	ea
MH, Standard SS (5')	7	ea
MH, Outside Drop Constructed (5')	1	ea
MH, Joint Wrap	629	lf
Riser Assembly 4", Manhole Stub	13	ea
Riser Assembly 4", Vertical	6	ea
Riser Assembly 8", Cleanout	1	ea
Pipe Stub, 8"	3	ea
Fill, Flowable	287	lf
Fill, Sand (Flushed & Vibrated)	1,209	lf
Maintain Existing BMPs	1	LS
Seeding	1	LS
Site Clearing	1	LS
Site Restoration	1	LS

#### **MEASURED QUANTITY BID ITEMS**

BMP, Construction Entrance	1	ea
----------------------------	---	----

\*\*\*\*\*

### PAVING PROJECT

#### Westgate, Greenfield

##### Southern Ridge 4th Addition

(south of Pawnee, west of Maize)

472-85045 490331

**Bid Date: 06-20-14; Award Date: 06-24-14**

#### **LUMP SUM BID ITEMS**

AC Pavement 5" (3" Bit Base)	2,665	sy
Crushed Rock Base (5"), Reinf.	3,240	sy
Comb. C&G, Type 2 (3 5/8" RL & 1 1/2")	1,480	lf
Concrete Sidewalk (4")	1,611	sf
Excavation	184	cy
Compacted Fill (95% Density)	226	cy
Borrow Excavation (Contractor furn'd)	318	cy
Signing	1	LS
Seeding	1	LS
Grading, Easement	1	LS
Site Clearing	1	LS
Site Restoration	1	LS

#### **MEASURED QUANTITY BID ITEMS**

BMP, Back of Curb Protection	1,480	lf
BMP, Drop Inlet Protection	6	ea
BMP, Ditch Check	1	ea
BMP, Construction Entrance	1	ea

\*\*\*\*\*

A minority/women-owned business is 51% owned and controlled by a minority or women. MBE/DBE classes are defined as: Asian (A) American Indian (AI) Black (B) Hispanic (H) and Women-owned (WO). We appreciate your cooperation in providing this information.