



BID BULLETIN



Upcoming Projects from Public Works–Engineering

General Information

The City of Wichita receives bids at the Purchasing office (455 N.Main, 12th Floor) up to 10:00 a.m. on the Friday specified for each project in this bulletin. All bids received online and/or on paper will thereafter be publicly opened, read aloud, and considered by the Board of Bids and by City Council. The Wichita City Council reserves the right to reject any and all bids.

Plans & Specifications for these projects are generally available 10 days prior to the bid date unless otherwise specified. All work is to be done under direction and supervision of the City Manager and according to the plans & specifications on file in the City Engineer's Office. Bidders are required to include a bid bond in the amount of five percent (5%) with each bid.

Requests for the bid documents & plans should be directed to City Blue Print Inc. (265-6224). Other questions should be directed to the project Engineer (268-4501).

The successful bidder may contact Kim Pelton (268-4499) for extra sets of plans/specs.

PAVING PROJECT (Deferred)

June 27, 2013

135th, Kellogg to Onewood (135th, north of Kellogg)

87N-0566-01/472-84915 210487/752035

Bid Date: 08-23-13; Award Date: Pending KDOT Approval

Lump Sum Bid Items - Paving (707022)

Mobilization	1	LS
Mobilization (DBE)	1	LS
Field Office & Laboratory (Type A)	1	ea
Site Clearing	1	LS
Site Restoration	1	LS
Removal of Existing Structures	1	LS
Concrete &/or Asphalt Pvmnt Removed	6,183	sy
Concrete Sidewalk Removed	19	sy
Excavation	5,926	cy
Excavation, Borrow (Contractor Furnished)	1,060	cy
Fill, Compacted (95% Density)	5,678	cy
AC Pavement 7" (5" Bit Base) (BM-2)	8,479	sy
Crushed Rock Base 8", Reinforced	10,133	sy
Concrete C&G, Comb Type I (6" & 1-1/2")	4,251	lf
Wheelchair Ramp w/Detectable Warnings	1	ea
Signing	1	LS
Pavement Marking	1	LS
Traffic Control	1	LS

Lump Sum Bid Items - Drainage (707022)

Inlet, Curb (Type 1) (L=5' W=3')	4	ea
Inlet, Curb (Type 1) (L=10' W=3')	13	ea
Inlet, Curb (Type 1) (L=10' W=4')	2	ea
Inlet Hookup	19	ea
MH, Reinforced Concrete (4' x 4')	2	ea
Pipe, PVC 4", Perforated (Inlet Underdrain)	209	lf
Pipe, SWS 15"	400	lf
Pipe, SWS 15" (RCP)	781	lf
Pipe, SWS 18"	375	lf
Pipe, SWS 18" (RCP)	44	lf
Pipe, SWS 24" (RCP)	87	lf
Pipe, SWS 30" (RCP)	53	lf
Pipe, Entrance 15"	72	lf
Pipe, 15" End Section	4	ea
Pipe, RCBC (2-10' x 6') w/ Wingwalls (Sta. 220+25)	106	lf
Handrail (Steel), Pedestrian (3'-6") (Sta. 220+25)	104	lf
Pipe, RCBC (4' x 3') w/ Wingwalls (Sta. 226+05)	91	lf
Handrail (Steel), Pedestrian (3'-6") (Sta. 226+05)	49	lf
Fill, Sand (Flushed & Vibrated)	1,161	lf

Continued on Page 2

Page 1 of 2

NOTE: All information contained herein is subject to change.

A minority/women-owned business is 51% owned and controlled by a minority or women. MBE/DBE classes are defined as: Asian (A) American Indian (AI) Black (B) Hispanic (H) and Women-owned (WO). We appreciate your cooperation in providing this information.



BID BULLETIN



Upcoming Projects from Public Works–Engineering

General Information

The City of Wichita receives bids at the Purchasing office (455 N.Main, 12th Floor) up to 10:00 a.m. on the Friday specified for each project in this bulletin. All bids received online and/or on paper will thereafter be publicly opened, read aloud, and considered by the Board of Bids and by City Council. The Wichita City Council reserves the right to reject any and all bids.

Plans & Specifications for these projects are generally available 10 days prior to the bid date unless otherwise specified. All work is to be done under direction and supervision of the City Manager and according to the plans & specifications on file in the City Engineer's Office. Bidders are required to include a bid bond in the amount of five percent (5%) with each bid.

Requests for the bid documents & plans should be directed to City Blue Print Inc. (265-6224). Other questions should be directed to the project Engineer (268-4501).

The successful bidder may contact Kim Pelton (268-4499) for extra sets of plans/specs.

NOTE: All information contained herein is subject to change.

PAVING PROJECT

June 27, 2013

135th, Kellogg to Onewood (135th, north of Kellogg)

87N-0566-01/472-84915 210487/752035

Continued from Page 1

Lump Sum Bid Items - Landscaping (707022)

Seeding	1	LS
Sodding, Fescue	1	LS

Measured Qty Bid Items - Paving (707022)

Concrete Sidewalk 4"	12,866	sf
Concrete Sidewalk 5"	22,098	sf
Concrete Sidewalk Protection Curb	70	lf
Concrete Driveway 8" (Reinforced)	5,546	sf
Surfacing Material 2" (SA-1) (Driveway)	1,300	sf
AC Pvmnt 6" (4" Bit Base), Temp for Widening (w/5" Crushed Rock Base)	354	sy
AC Pvmnt 6", Temp for Patching	117	sy
Riprap, Light Stone	393	sy
Sign, Electronic Portable Message	50	day

Measured Qty Bid Items - Erosion Control BMP (707022)

BMP, Curb Inlet Protection	19	ea
BMP, Silt Fence	4,250	lf
BMP, Construction Entrance	2	ea
BMP, Back of Curb Protection	4,081	lf

Measured Qty Bid Items - Landscaping (707022)

Tree, Japanese Tree Lilac - 2.5" caliper	12	ea
Tree, Oklahoma Redbud - 2.5" caliper	14	ea
Tree, Professor Sprenger Crabapple - 2.5" caliper	20	ea
Tree, Zumi Crabapple - 2.5" caliper	16	ea
Tree, Goldenraintree - 2.5" caliper	7	ea
Tree, Hedge Maple - 2.5" caliper	7	ea
Tree, Chinquapin Oak - 3" caliper	13	ea

Water Improvements (Non-Participating)

Measured Qty Bid Items (635813)

Pipe, WL 16"	1,778	lf
Pipe, DI CL RJ 16"	113	lf
Pipe, DI CL SJ 16"	48	lf
Valve Assembly, Anchored, 16"	2	ea
Valve Assembly, 16"	1	ea
Fire Hydrant Assembly	4	ea
Fill, Sand (Flushed & Vibrated)	82	lf
Conc. Pvmnt. Rem. - Asph. Repl.	30	lf
Concrete Driveway Rem & Repl	30	lf
Gravel Streets/Drives Rem & Repl	41	lf
BMP, Silt Fence	346	lf

Page 2 of 2

A minority/women-owned business is 51% owned and controlled by a minority or women. MBE/DBE classes are defined as: Asian (A) American Indian (AI) Black (B) Hispanic (H) and Women-owned (WO). We appreciate your cooperation in providing this information.