



BID BULLETIN



Upcoming Projects from Public Works–Engineering

General Information

The City of Wichita receives bids at the Purchasing office (455 N.Main, 12th Floor) up to 10:00 a.m. on the Friday specified for each project in this bulletin. All bids received online and/or on paper will thereafter be publicly opened, read aloud, and considered by the Board of Bids and by City Council. The Wichita City Council reserves the right to reject any and all bids.

Plans & Specifications for these projects are generally available 10 days prior to the bid date unless otherwise specified. All work is to be done under direction and supervision of the City Manager and according to the plans & specifications on file in the City Engineer's Office. Bidders are required to include a bid bond in the amount of five percent (5%) with each bid.

Requests for the bid documents & plans should be directed to City Blue Print Inc. (265-6224). Other questions should be directed to the project Engineer (268-4501).

The successful bidder may contact Kim Pelton (268-4499) for extra sets of plans/specs.

NOTE: All information contained herein is subject to change.

May 20, 2010

PAVING PROJECTS

2010 Arkansas Bridge Deck Rehabilitation (Arkansas & 40th Street North)

472-84903

Bid Date: 06-04-10; Award Date: 06-08-10

Measured Quantity Bid Items

Cold Milling Concr Bridge Deck (Approx. 1 1/2"-2" in Concr)	1,137	sy
Reinf. Steel (Set) (GR 60) (For Deck Repairs)	150	lb
Partial Depth Patching	380	sy
Full Depth Patching	20	sy
Joint Sealer (DOW 888)	112	lf
Silica Fume Concr Overlay (2" min. Depth)	1,137	sy
6" White or Yellow Pvmnt Mrkgs (Thermopl.)	800	lf
10" Conc Approach (Reinf 2 Layers & J Hooks)	374	sy
Traffic Control Arkansas Bridge	1	LS

Lark Court

Steve Kelley 6th Addition

472-84889 490270

Bid Date: 06-04-10; Award Date: 06-08-10

Lump Sum Bid Items

AC Pavement 5" (3" Bit Base)	550	sy
Crushed Rock Base 5", Reinf	776	sy
Concrete Pavement (VG) 7", Reinf	101	sy
Concrete C&G, Comb. Type 3 (3 5/8" RL & 1 1/2")	306	lf
Concr Curb, Mono Edge (6-5/8" & 1-1/2")	63	lf
Excavation, Borrow (Contr. Furn'd)	445	cy
Excavation, Unclassified	323	cy
Fill, Compacted (95% Density)	399	cy
Maintain Existing BMPs	1	LS
Grading, Easement	1	LS
Signing	1	LS
Seeding	1	LS
Site Clearing	1	LS
Site Restoration	1	LS

Measured Quantity Bid Items

BMP, Back of Curb Protection	369	LF

WATER-PAVING PROJECT

Water Distribution System

Firepoint Addition

448-90470 470116 TIED WITH

Toben

Firepoint Addition

472-84885 490268

Bid Date: 06-04-10; Award Date: 06-08-10

GROUP 1 LUMP SUM ITEMS (735443)

Mobilization	1	LS
WL Pipe 12"	495	lf
WL Pipe 12", DICL	14	lf
Fire Hydrant Assembly	1	ea
Valve Assembly, Anchored, 12"	1	ea
Site Clearing	1	LS
Site Restoration	1	LS
Seeding	1	LS

GROUP 2 LUMP SUM ITEMS (766250)

AC Pavement 7" (5" Bit Base)	2,043	sy
Reinf Crushed Rock Base (6")	2,542	sy
Concrete Pvmnt (VG) 7" (Reinf)	86	sy
Comb. C & G (6 5/8" & 1 1/2")	988	lf
Mono Edge Curb (3 5/8" RL & 1 1/2")	63	lf
MH, Reinforced Concrete	3	ea
MH, Type P, Standard (6')	1	ea
Concrete C & G Removed	80	lf
Hedge Row Removed	100	lf
Pipe, RCP, 36"	13	lf
Pipe, RCBC (6' x 8")	150	lf
Pipe, RCBC (4' x 8")	80	lf
Remove Exist. Wingwalls & Toe Walls	1	LS
Fill, Sand, Flushed and Vibrated	83	lf
Excavation	1,450	cy
Compacted Fill (95% Density)	2,725	cy
Site Clearing	1	LS
Site Restoration	1	LS
Seeding	1	LS

GROUP 2 MEASURED QTY ITEMS (766250)

BMP, Linear Sediment Barrier	1,070	lf

A minority/women-owned business is 51% owned and controlled by a minority or women. MBE/DBE classes are defined as: Asian (A) American Indian (AI) Black (B) Hispanic (H) and Women-owned (WO). We appreciate your cooperation in providing this information.