



## **SPILL PREVENTION AND COUNTERMEASURE PLAN (SPCP)**

A Spill Prevention and Countermeasure Plan (SPCP) is required of all industries that store solvents and/or hazardous material that could be accidentally spilled into the sanitary sewer.

The Plan shall contain, at a minimum, the following elements;

1. Description of discharge practices, including non-routine batch discharges.
2. Description of stored chemicals and/or hazardous material.
3. Procedures for immediately notifying the Public Owned Treatment Works (POTW) of slug discharges and/or accidental spills, including any discharge that would violate a prohibition under the City of Wichita Ordinance Code, Section 17.20.060 and EPA 40 CFR Part 403.5(b), with procedures for follow-up written notification within five days.
4. Procedures to prevent adverse impact from accidental spills to include:
  - a. Inspection and maintenance of storage areas.
  - b. Handling and transfer of materials.
  - c. Loading and unloading operations.
  - d. Control of plant site run-off.
  - e. Worker training
  - f. Building of containment structures or equipment.
  - g. Measures for containing toxic organic pollutants (including solvents).
  - h. Measures and equipment for emergency response.
  - i. Posting of signs with telephone numbers of key industrial personnel and/or POTW pretreatment personnel to be notified in case of a slug discharge and/or accidental spill.