

MORE UPCOMING ENGINEERING PROJECTS

General Information

The City of Wichita receives bids at the Purchasing office (455 N.Main, 12th Floor) up to 10:00 a.m. on the Friday this bulletin. All bids received online and/or on paper will thereafter be publicly opened, read aloud, and considered by the Board of Bids and by City Council. The Wichita City Council reserves the right to reject any and all bids.

Plans & Specifications for these projects are generally available 10 days prior to the bid date unless otherwise specified. All work is to be done under direction and supervision of the City Manager and according to the plans & specifications on file in the City Engineer's Office. Bidders are required to include a bid bond in the amount of five percent (5%) with each bid.

Requests for the bid documents & plans should be directed to CBP

Reprographics (265-6224). Other questions should be directed to the project Engineer (268-4501).

The successful bidder may contact Kim Pelton (268-4499) for extra sets of plans/specs.

CITY / KDOT PAVING PROJECT to bid DECEMBER 11, 2009

Hydraulic, Harry to Kellogg (KDOT)

87N-0503-01/472-84848 - /669664/779609

Bid Date: 12-11-09; Award Date: After 12-08-09

Lump Sum Items - Paving (991304)

Field Office & Lab (Type A)	1	ea
Mobilization	1	LS
Mobilization (DBE)	1	LS
Site Clearing & Preparation	1	LS
Site Restoration	1	LS
Removal of Existing Structures	1	LS
Pavement Removal (Includes Curb & Gutter)	23,367	sy
Prkg Lot, Sdwk & Drvwy Removal (Conc. & Asphalt)	8,116	sy
Excavation	7,707	cy
Compacted Fill	128	cy
Concrete Pavement (9") (Reinf) (AE)	4,050	sy
Concrete Pavement (8") (NRDJ) (AE)	18,796	sy
RCVG Pavement (8") (AE)	1,724	sy
Concrete Pavement (8") (AE)	140	sy
AC Pvmt Surface (2") (BM-2) (PG 70 - 28)	1,088	sy
Reinf Crushed Rock Base (6")	4,140	sy
Reinf Crushed Rock Base (5")	24,225	sy
C&G (Comb.) (Type I) (6" & 1 1/2") (AE)	9,816	lf
Curb & Gutter (Combined) (Type III) (8") (AE)	544	lf
Monolithic Edge Curb (6") (AE)	982	lf
Solid Conc.Median Ramp-type Nose Section	4	ea
Wheelchair Ramps	40	ea
Paving Brick (3 1/8 in) (Crosswalk) (Incl. Sand Base)	577	sy
Paving Brick (2 3/8 in) (Median) (Incl. Sand Base)	969	sf
Concrete Median Surface (4")	1,549	sf
Cold Milling (2")	1,088	sy
Concrete Inlet Hookups	30	ea
Sodding	7,270	sy
Lump Sum Bid Items - Drainage		
Inlet (Curb) (Type 1) (Single) (L= 5' W= 3')	3	ea
Inlet (Curb) (Type 1) (Single) (L= 5' W= 4')	2	ea
Inlet (Curb) (Type 1) (Double) (L= 10' W= 2.5') (Special)	2	ea
Inlet (Curb) (Type 1) (Double) (L=10' W= 3')	7	ea
Inlet (Curb) (Type 1) (Double) (L=10' W=4')	3	ea
Inlet (Curb) (Type 1a) (Double) (L=10' W=2.5') (Special Setback)	6	ea
Inlet (Curb) (Type 1a) (Single) (L=5' W=3')	3	ea
Inlet (Curb) (Type 1a) (Double) (L=10' W= 3')	1	ea
Inlet (Curb) (Type 2) (Double)	3	ea
Inlet (Driveway) (Double)	1	ea
Reinf. Conc. Manhole (6'x6')	1	ea
Reinf. Conc. Manhole (7'x7')	1	ea
Manhole (Std Type P) (5' Dia.)	1	ea
Manhole (Std Shallow Type P) (5' Dia.)	2	ea
Manhole (Std Shallow Type P) (4' Dia.)	2	ea

(Cont'd on Next Page)

Page 1 of 3

NOTE: All information contained herein is subject to change.

A minority/women-owned business is 51% owned and controlled by a minority or women. MBE/DBE classes are defined as: Asian (A) American Indian (AI) Black (B) Hispanic (H) and Women-owned (WO). We appreciate your cooperation in providing this information.

MORE UPCOMING ENGINEERING PROJECTS

General Information

The City of Wichita receives bids at the Purchasing office (455 N.Main, 12th Floor) up to 10:00 a.m. on the Friday specified for each project in this bulletin. All bids received online and/or on paper will thereafter be publicly opened, read aloud, and considered by the Board of Bids and by City Council. The Wichita City Council reserves the right to reject any and all bids.

Plans & Specifications for these projects are generally available 10 days prior to the bid date unless otherwise specified. All work is to be done under direction and supervision of the City Manager and according to the plans & specifications on file in the City Engineer's Office. Bidders are required to include a bid bond in the amount of five percent (5%) with each bid.

Requests for the bid documents & plans should be directed to CBP Reprographics (265-6224). Other questions should be directed to the project Engineer (268-4501).

The successful bidder may contact Kim Pelton (268-4499) for extra sets of plans/specs.

Hydraulic, Harry to Kellogg (KDOT)

Lump Sum Items - Paving (991304)

(CONT'D)

Storm Sewer (6") (PVC)	15	ea
Storm Sewer (12") (DICL)	210	ea
Storm Sewer (12") (C 900 W/L)	356	lf
Storm Sewer (15") (RCP)	1,012	lf
Storm Sewer (18") (RCP)	1,419	lf
Storm Sewer (24") (RCP)	816	lf
Storm Sewer (30") (RCP)	836	lf
Manhole Reconstructed W/New Ring & Cover	1	ea
Manholes Abandoned	3	ea
Storm Sewer Pipe Abandoned in Place	1,712	lf

Lump Sum Bid Items - Traffic

Pavement Marking	1	LS
Project Signage	1	LS
Temporary Signalization (2 Locations)	1	LS
Traffic Signalization at Hydraulic & Harry	1	LS
Traffic Signalization at Hydraulic & Lincoln	1	LS
Traffic Control (Construction)	1	LS

Lump Sum Bid Items - Non-Standard

Transp. of Salvageable Material (non-participating)	1	LS
Water Valve Adjustment (non-participating)	1	LS

Measured Quantity Bid Items - Paving (991304)

Sidewalk Concrete (4")	42,029	sf
Driveway Concrete Pvmt, 8" (Reinf.)(AE)	38,128	sf
AC Parking Lot Pvmt (5")	800	sf
Temporary Asphalt Pavement (6")	270	sy
Crushed Rock Hookup Surface (6") (Drive Hookup)	336	sf
Protection Curb	142	lf
Manhole Adjustments w/New Ring & Cover	13	ea
Manhole Adjustments w/o New Ring & Cover	11	ea
Metal Plate AT&T Manhole Cover (Furnish & Install)	1	ea
AT&T Manholes Adjusted	13	ea
Concrete Flume w/Sidewalk Section	11	lf
Sand Fill, Flush & Vibrate	4,649	lf

Measured Quantity Bid Items - Miscellaneous

Small Tree Removal	13	ea
Large Tree Removal	31	ea
Portable, Changeable Electronic Message Boards	100	dy

Measured Quantity Bid Items - BMPs

Erosion Control BMP (Back of Curb Protection)	5,800	sy
Erosion Control BMP (Inlet Protection)	39	ea
Erosion Control BMP (Stablized Construction Entrance)	8	ea

Water Improvements (Non-Participating)

Measured Quantity Bid Items (636220)

2" Water Pipe	18	lf
6" Water Pipe	33	lf
8" Water Pipe	5,580	lf
6" DICL Water Pipe	27	lf
8" DICL Water Pipe	188	lf

(Cont'd on Next Page)

NOTE: All information contained herein is subject to change.

A minority/women-owned business is 51% owned and controlled by a minority or women. MBE/DBE classes are defined as: Asian (A) American Indian (AI) Black (B) Hispanic (H) and Women-owned (WO). We appreciate your cooperation in providing this information.

MORE UPCOMING ENGINEERING PROJECTS

General Information

The City of Wichita receives bids at the Purchasing office (455 N.Main, 12th Floor) up to 10:00 a.m. on the Friday specified for each project in this bulletin. All bids received online and/or on paper will thereafter be publicly opened, read aloud, and considered by the Board of Bids and by City Council. The Wichita City Council reserves the right to reject any and all bids.

Plans & Specifications for these projects are generally available 10 days prior to the bid date unless otherwise specified. All work is to be done under direction and supervision of the City Manager and according to the plans & specifications on file in the City Engineer's Office. Bidders are required to include a bid bond in the amount of five percent (5%) with each bid.

Requests for the bid documents & plans should be directed to CBP Reographics (265-6224). Other questions should be directed to the project Engineer (268-4501).

The successful bidder may contact Kim Pelton (268-4499) for extra sets of plans/specs.

Hydraulic, Harry to Kellogg (KDOT)

Measured Quantity Bid Items (636220) (CONT'D)

6" Valve Assy (Gate Valve)	3	ea
6" Anchored Valve Assy (Gate Valve)	1	ea
8" Valve Assy (Gate Valve)	10	ea
8" Anchored Valve Assy (Gate Valve)	6	ea
2" Service Outlet Assy	2	ea
Fire Hydrant Assy	7	ea
Fire Hydrants Removal	7	ea
2" Blow-Off Assy	5	ea
Sand Fill, Flush & Vibrate	680	lf
Conc. Sanitary Sewer Encasement	20	lf
Temporary Asphalt Pavement (6")	762	sy
Remove Existing Water Valves	2	ea
Abandon Existing Water Valves	19	ea
Reloc. & Re-install Water Services (Short)	84	ea
Reloc. & Reinstall Water Services (Long)	72	ea

Sanitary Sewer Improvements (Non-Participating)

Lump Sum Bid Items (620546)

18" PVC SS Pipe (Incl. Removal of Exist. Pipe)	58	lf
30" PVC SS Pipe (Incl. Removal of Exist. Pipe)	479	lf
Reinf. Concrete Manholes (6'-6"x4')	2	ea
Remove Manhole	3	ea
Temporary Asphalt Pvmt (6")	300	sy
By-Pass Pumping	1	LS
Sand Fill, Flush & Vibrate	498	lf

NOTE: All information contained herein is subject to change.

A minority/women-owned business is 51% owned and controlled by a minority or women. MBE/DBE classes are defined as: Asian (A) American Indian (AI) Black (B) Hispanic (H) and Women-owned (WO). We appreciate your cooperation in providing this information.