

MORE UPCOMING ENGINEERING PROJECTS

General Information

The City of Wichita receives bids at the Purchasing office (455 N.Main, 12th Floor) up to 10:00 a.m. on the Friday this bulletin. All bids received online and/or on paper will thereafter be publicly opened, read aloud, and considered by the Board of Bids and by City Council. The Wichita City Council reserves the right to reject any and all bids.

Plans & Specifications for these projects are generally available 10 days prior to the bid date unless otherwise specified. All work is to be done under direction and supervision of the City Manager and according to the plans & specifications on file in the City Engineer's Office. Bidders are required to include a bid bond in the amount of five percent (5%) with each bid.

Requests for the bid documents & plans should be directed to City Blue Print Inc. (265-6224). Other questions should be directed to the project Engineer (268-4501).

The successful bidder may contact Kim Pelton (268-4499) for extra sets of plans/specs.

CITY / KDOT PAVING PROJECT to bid OCTOBER 27, 2006

37th Street North, Tyler to Ridge

87N-0346-01/472-84184 (706920)

Bid Date: 10-27-06; Award Date: 11-07-06

Lump Sum Bid Items - Paving

Field Office & Lab (Type A)	1	ea
Mobilization	1	LS
Mobilization (DBE)	1	LS
R/W Clearing & Site Preparation	1	LS
Site Restoration	1	LS
Permanent Seeding	21,950	sy
Sodding	9,420	sy
Removal of Existing Structures	1	LS
Removal of Asphalt Pvmnt	20,536	sy
Removal of Concr Pvmnt (incl C&G)	122	sy
Common Excavation	15,980	cy
Compacted Fill (Type B) (MR-90)	21,175	cy
Borrow Excav. (Contractor Furn'd)	11,560	cy
Select Fill Topsoil (Medians)	745	cy
AC Pvmnt (7") (5" Bit. Base) (BM-2) (PG 70-28)	36,353	sy
Reinf. Concr Pvmnt (10") (Class A) (AE) - Bridge Approach Slabs	411	sy
Reinf. Concr Pvmnt (9") (Class A) (AE) - Tyler/Ridge Intersections	3,078	sy
Reinf. Concr Pvmnt (8") (Class A) (AE) - Valley Gutters/RR Approach Slabs	1,713	sy
Reinf Crushed Rock Base (8") (incl Geogrid Reinf.)	42,207	sy
Reinf Crushed Rock Base (7") (incl Geogrid Reinf.)	1,636	sy
Reinf Crushed Rock Base (6") (incl Geogrid Reinf.)	3,368	sy
Comb C&G (Type I) (6") (AE)	10,804	ft
Comb C&G (Type III) (8") (AE)	3,824	ft
Monolithic Edge Curb (6") (AE)	556	ft
Std Wheelchair Ramps (6')	18	ea
Paving Bricks (3 1/8") (Crosswalks) (Red) (Plaza Stone (Plaza 1))	425	sy
Paving Bricks (2 3/8") (Medians) (Red) (Appian Stone)	465	sy
Bridge Approach Slab Footing	32	cy
Concr Safety Barrier (Special)(AE)	134	ft
Modular Block Retaining Wall	15	lf

Lump Sum Bid Items - Bridge

Excavation - Class I	194	cy
Excavation - Class II	156	cy
Concr Grade 4.0 (AE)	101	cy
Concr Grade 4.0 (AE) (SA)	751	cy
Reinf. Steel (Grade 60)	7,900	lbs
Reinf. Steel (Grade 60) (Epoxy Coated)	158,130	lbs
Bridge Backwall Prot. System	80	sy
Abutment Strip Drain	65	sy
Bridge Handrail (Steel)(Pedestrian)(Opt. A)	325	ft
Rip-Rap (Grouted Light Stone)	242	cy
Rip-Rap (Light Stone)	141	cy
Bridge Drain	8	ea
2" R.G.C.	226	ft
Contractor Staking - Bridge	1	LS

(Cont'd)

Page 1 of 3

NOTE: All information contained herein is subject to change.

A minority/women-owned business is 51% owned and controlled by a minority or women. MBE/DBE classes are defined as: Asian (A) American Indian (AI) Black (B) Hispanic (H) and Women-owned (WO). We appreciate your cooperation in providing this information.

MORE UPCOMING ENGINEERING PROJECTS

General Information

The City of Wichita receives bids at the Purchasing office (455 N.Main, 12th Floor) up to 10:00 a.m. on the Friday specified for each project in this bulletin. All bids received online and/or on paper will thereafter be publicly opened, read aloud, and considered by the Board of Bids and by City Council. The Wichita City Council reserves the right to reject any and all bids.

Plans & Specifications for these projects are generally available 10 days prior to the bid date unless otherwise specified. All work is to be done under direction and supervision of the City Manager and according to the plans & specifications on file in the City Engineer's Office. Bidders are required to include a bid bond in the amount of five percent (5%) with each bid.

Requests for the bid documents & plans should be directed to KBP Reprographics (264-9344). Other questions should be directed to the project Engineer (268-4501).

The successful bidder may contact Kim Pelton (268-4499) for extra sets of plans/specs.

37th Street North, Tyler to Ridge

Measured Quantity Bid Items - Bridge

Pile (Concr 14" Shell)	3,643	ft
------------------------	-------	----

Lump Sum Bid Items - Drainage

Inlet Curb (Type 1A) (6' 4" X 4' 4")	2	ea
Inlet Curb (Type 1A) (11' 4" X 4' 4")	8	ea
Inlet Curb (Type 1A) (11' 4" X 5' 4")	1	ea
Inlet Curb (Type 1A) (11' 4" X 6' 4")	3	ea
Inlet Curb (Type 1A) (11' 4" X 7' 4")	3	ea
Inlet Curb (Type 1) (6' 4" X 6' 4")	1	ea
Inlet Curb (Type 1) (11' 4" X 4' 4")	1	ea
Inlet Curb (Type 1) (11' 4" X 6' 4")	2	ea
MH (Std Type "P") (6' Dia.)	3	ea
MH (Reinf Concr) (8' 4" X 8' 4")	2	ea
MH (Reinf Concr) (11' 4" X 7' 4")	1	ea
MH (Spec.Shallow Type P) (4' Dia.)	1	ea
MH (Shallow Type P) (4' Dia.)	2	ea
MH (Shallow Type P) (5' Dia.)	1	ea
MH (Shallow Type P) (6' Dia.)	4	ea
Storm Sewer (15") (RCP) (incl End Sections)	958	ft
Storm Sewer (14" X 23") (HERCP) (incl End Sections)	272	ft
Storm Sewer (18") (RCP) (incl End Sections)	333	ft
Storm Sewer (19" X 30") (HERCP)	85	ft
Storm Sewer (24") (RCP) (incl End Section)	262	ft
Storm Sewer (24" X 38") (HERCP)	464	ft
Storm Sewer (30") (RCP)	301	ft
Storm Sewer (36") (RCP)	375	ft
Storm Sewer (42") (RCP)	1,998	ft
Storm Sewer (48") (RCP) (Installed by Trenchless Methods)	270	ft
Storm Sewer (48") (RCP)	1,289	ft
Storm Sewer (54") (RCP)	342	ft
Storm Sewer (60") (RCP)	428	ft
Wingwalls (42" RCP)	1	ea
Wingwalls (60" RCP)	1	ea
Light Stone Rip-Rap	86	sy
Heavy Stone Rip-Rap	32	sy

Lump Sum Bid Items - Traffic

Pvmt Marking	1	LS
Project Signage	1	LS
Traffic Control (Construction)	1	LS
Traffic Signal Interconnect	1	LS
Traffic Signalization (37th St N & Ridge Rd)	1	LS
Traffic MHs & Conduit (37th St N & Tyler)	1	LS

Lump Sum Bid Items - Landscaping

Project Erosion Control	1	LS
Landscaping	1	LS

(Cont'd)

NOTE: All information contained herein is subject to change.

A minority/women-owned business is 51% owned and controlled by a minority or women. MBE/DBE classes are defined as: Asian (A) American Indian (AI) Black (B) Hispanic (H) and Women-owned (WO). We appreciate your cooperation in providing this information.

MORE UPCOMING ENGINEERING PROJECTS

General Information

The City of Wichita receives bids at the Purchasing office (455 N.Main, 12th Floor) up to 10:00 a.m. on the Friday specified for each project in this bulletin. All bids received online and/or on paper will thereafter be publicly opened, read aloud, and considered by the Board of Bids and by City Council. The Wichita City Council reserves the right to reject any and all bids.

Plans & Specifications for these projects are generally available 10 days prior to the bid date unless otherwise specified. All work is to be done under direction and supervision of the City Manager and according to the plans & specifications on file in the City Engineer's Office. Bidders are required to include a bid bond in the amount of five percent (5%) with each bid.

Requests for the bid documents & plans should be directed to KBP Reprographics (264-9344). Other questions should be directed to the project Engineer (268-4501).

The successful bidder may contact Kim Pelton (268-4499) for extra sets of plans/specs.

37th Street North, Tyler to Ridge

Measured Quantity Bid Items

AC Pvm (6") (Drive) (BM-2)	888	sf
Reinf. Concr Pvm (8") (Drives) (Class A) (AE)	1,931	sf
Sidewalk Concr (4")	62,913	sf
Protection Curb (6" & 8")	654	ft
Crushed Rock Surface (6") (Drive Hook-up)	1,810	sf
Sand Fill, Flushed & Vibrated	7,050	ft

Non-Participating Bid Items

Transp. of Salvageable Material	1	LS
Adj of Water Valves	1	LS
Adj of SS MHs	7	ea
Project Signage (D-3 Metro Street Name Signs)	1	LS
Private Sprinkler System Restoration	1	LS
PVC Pipe Irrigation Sleeves (6")	136	ft
Water Pipe (8") (DACL)	59	ft
Water Pipe (16") (DACL)	34	ft
Fire Hydrant Adjustments	2	ea
Fire Hydrant Relocations	3	ea
Bridge Plaque	1	ea

Add Alternate Bid Item (Non-Participating)

Bridge Handrail (Steel)(Pedestrian)(Opt. B) upgrade cost	1	LS
--	---	----

NOTE: All information contained herein is subject to change.

A minority/women-owned business is 51% owned and controlled by a minority or women. MBE/DBE classes are defined as: Asian (A) American Indian (AI) Black (B) Hispanic (H) and Women-owned (WO). We appreciate your cooperation in providing this information.