



BID BULLETIN

Upcoming Projects from Public Works–Engineering



General Information

The City of Wichita receives bids at the Purchasing office (455 N.Main, 12th Floor) up to 10:00 a.m. on the Friday specified for each project in this bulletin. All bids received online and/or on paper will thereafter be publicly opened, read aloud, and considered by the Board of Bids and by City Council. The Wichita City Council reserves the right to reject any and all bids.

Plans & Specifications for these projects are generally available 10 days prior to the bid date unless otherwise specified. All work is to be done under direction and supervision of the City Manager and according to the plans & specifications on file in the City Engineer's Office. Bidders are required to include a bid bond in the amount of five percent (5%) with each bid.

Requests for the bid documents & plans should be directed to City Blue Print Inc. (265-6224). Other questions should be directed to the project Engineer (268-4501).

The successful bidder may contact Kim Pelton (268-4499) for extra sets of plans/specs.

NOTE: All information contained herein is subject to change.

PAVING PROJECTS

2004/2005 Traffic Signal. Prog. Ph VI
Traffic signals at 21st & Founder's Circle
 472-84402 204377

Bid Date: 04-14-06; Award Date: 04-18-06

Lump Sum Bid Items

Traffic Signalization 1 LS

Village Parkway
North Ridge Village Addition
 472-84201 490052

Bid Date: 04-14-06; Award Date: 04-18-06

Lump Sum Bid Items

AC Pvmt 6" (4" Bit Base)	6,833	sy
Reinf Crushed Rock Base (6")	9,906	sy
RCVG Pvmt (6")	195	sy
Concr Pvmt (6") (Reinforced)	255	sy
Comb C&G (3 5/8" RL & 1 1/2")	490	lf
Comb C&G (6 5/8" & 1 1/2")	3,220	lf
Median Comb C&G (8")	3,026	lf
Mono Edge Curb (6 5/8" & 1 1/2")	110	lf
Sidewalk Concr (4")	7,701	sf
Wheelchair Ramp Constr (30 sf)	6	ea
Inlet Hookup	11	ea
Excavation	35	cy
Borrow Excav (Contr. Furn'd)	23,605	cy
Compacted Fill (90% Density)	7,900	cy
Compacted Fill (95% Density)	11,800	cy
Ditch Grading	230	lf
Sediment Barrier, Inlet	11	ea
Sediment Barrier, Hay Bale	5	ea
Concr Slope Drain	46	lf
Site Clearing & Restoration	1	LS
Project Seeding	1	LS
BMP	1	LS
6" PVC Sleeves	1,089	lf
Street Signage	1	LS
Traffic Control	1	LS
SWS Pipe RCP 15"	241	lf
SWS Pipe RCP 24"	289	lf
SWS Pipe RCP 30"	311	lf
SWS Pipe RCP 36"	275	lf
SWS Pipe RCP 42" (incl. end sect.)	670	lf

(Cont'd in Next Column)

Village Parkway (Cont'd)
North Ridge Village Addition

Lump Sum Bid Items

Inlet, Curb 1A (L=5' W=3')	4	ea
Inlet, Curb 1A (L=5' W=4')	2	ea
Inlet, Curb 1A (L=5' W=5')	3	ea
Inlet, Curb 1A (L=10' W=6')	1	ea
MH, Shallow Type B, 6' Dia	1	ea
MH, Shallow Type A, 6' Dia	1	ea
Rip-Rap, (5" x 9")	95	sy
Flowable Fill	738	lf
Inlet, Curb Type 1 (L=10' W=3')	1	ea

SEWER PROJECTS

Lat. 1, Main 23 Southwest Interceptor Sewer
Emerald Bay Estates Addition
 468-84139 480858

Bid Date: 04-14-06; Award Date: 04-18-06

Lump Sum Bid Items

SS Pipe PVC 8"	6,545	lf
MH, Std	10	ea
MH, Type P or C (Std), D=5'	17	ea
MH, Type P or D (Std) (outside drop), D=5'	4	ea
Stub, SS 8"	2	ea
Stub, SS 10"	1	ea
Cleanout /Riser Assy 8"	6	ea
Riser Pipe Assy 4"	52	ea
Sand fill trench, flush & vibrate	6,004	lf
Casing Bored & Jacked (18" ID min.), Steel	154	lf
Site Clearing & Restoration	1	LS
Flowable Fill	387	lf
Erosion Control BMP	1	LS

A minority/women-owned business is 51% owned and controlled by a minority or women. MBE/DBE classes are defined as: Asian (A) American Indian (AI) Black (B) Hispanic (H) and Women-owned (WO). We appreciate your cooperation in providing this information.

MORE UPCOMING ENGINEERING PROJECTS

General Information

The City of Wichita receives bids at the Purchasing office (455 N.Main, 12th Floor) up to 10:00 a.m. on the Friday specified for each project in this bulletin. All bids received online and/or on paper will thereafter be publicly opened, read aloud, and considered by the Board of Bids and by City Council. The Wichita City Council reserves the right to reject any and all bids.

Plans & Specifications for these projects are generally available 10 days prior to the bid date unless otherwise specified. All work is to be done under direction and supervision of the City Manager and according to the plans & specifications on file in the City Engineer's Office. Bidders are required to include a bid bond in the amount of five percent (5%) with each bid.

Requests for the bid documents & plans should be directed to City Blue Print Inc. (265-6224). Other questions should be directed to the project Engineer (268-4501).

The successful bidder may contact Kim Pelton (268-4499) for extra sets of plans/specs.

Drainage Improv. 29th St. N. & Lake Ridge Rd Oak Ridge Addition

468-84164 856101

Bid Date: 04-14-06; Award Date: 04-18-06

Lump Sum Bid Items

Mobilization	1	LS
Clearing & Grubbing	1	LS
Common Excavation	190	CY
15" RCP	806	LF
Drop Inlet (2'x2')	3	EA
Erosion Control	1	LS
Site Restoration (hydro seed)	1	LS
Private Sprinkler Sys. Restoration	1	LS

Storm Water Drain #254

468-83978 485294 Tied With

Storm Water Drain #255

468-83979 485299

North Ridge Village Addition

Bid Date: 04-14-06; Award Date: 04-18-06

Lump Sum Bid Items (751403)

Excavation	49,000	cy
Borrow Excav (Contr. Furn'd)	1,040	cy
Compacted Fill (95% Density)	50,040	cy
Ditch Grading	1,800	lf
Sediment Barrier, Hay Bale	8	ea
Sediment Barrier, Silt Fence	3,430	lf
Site Clearing & Restoration	1	LS
Project Seeding	1	LS
BMP	1	LS
Stabilized Constr. Entrance	1	ea
Conservation Parcel Seeding	1	LS

Lump Sum Bid Items (751408)

Excavation	20,900	cy
Borrow Excav (Contr. Furn'd)	3,340	cy
Compacted Fill (95% Density)	20,200	cy
Sediment Barrier, Silt Fence	3,175	lf
Site Clearing & Restoration	1	LS
Project Seeding	1	LS
BMP	1	LS
Stabilized Constr. Entrance	1	ea
Conservation Parcel Seeding	1	LS

NOTE: All information contained herein is subject to change.

A minority/women-owned business is 51% owned and controlled by a minority or women. MBE/DBE classes are defined as: Asian (A) American Indian (AI) Black (B) Hispanic (H) and Women-owned (WO). We appreciate your cooperation in providing this information.