

TO BE PUBLISHED ONE TIME ON OCTOBER 9, 2019

SEALED PROPOSALS

Notice is hereby given that bids will be received at the office of the Purchasing Manager, up to 10:00 a.m., Friday, October 25, 2019 for the following project:

Harry St Bridge at Arkansas River

472-85359

LUMP SUM BID ITEMS - PAVEMENT

Mobilization	1	LS
Construction Staking	1	LS
Removal of Existing Structures	1	LS
Site Clearing	1	LS
Site Restoration	1	LS
Excavation	578	cy
Fill, Comp. (95% Density)	1,178	cy
Fill, Comp. (95% Density), Contr. Furn.	895	cy
Transport. of Salvaged Material	1	LS
Fiber Optic Cable Relocation	1	LS

MEASURED QTY BID ITEMS - PAVEMENT

Field Office and Lab (Type A)	1	ea
Pvmt Rem	490	sy
Conc C & G Rem	214	lf
Sidewalk, Drive, &/or Pkg. Lot Rem	410	sy
Brick Pavers Rem	49	sy
Brick Pavers Rem & Reset	24	sy
Concr Pvmt 12" (Bridge Approach)	200	sy
Concr Pvmt 9" (Reinf)	332	sy
Colored Concr Pvmt 5" (Reinf)	353	sy
Crushed Rock Base 6", Reinf	618	sy
Concr C & G, Type 1 (6")	177	lf
Concr Sidewalk 5"	9,875	sf
Concr Sidewalk 4"	224	sf
Sidewalk Thickened Edge	168	lf
WCR w/Det Warn Panels	3	ea
Concr (Grade 4.0) (AE)	9	cy
Reinf Steel (Grade 60)(Epoxy Coated)	2,870	lb
Bridge Approach Slab Footing	35	cy

LUMP SUM BID ITEMS - BRIDGE

Excavation (Class I)	455	cy
Excavation (Class II)	1,023	cy
Concr (Grade 4.0)(AE)	909	cy
Concr (Grade 4.0)(AE) (SA)	818	cy
Reinf Steel(Grade 60)	129,870	lb
Reinf Steel(Grade 60)(Epoxy Coated)	259,810	lb

Piles (Steel)(HP12x53)	4,764	lf
Test Piles (Steel)(HP12x53)	368	lf
Abutment Aggregate Drain	1,070	cy
Bridge Backwall Prot. System	367	sy
Prestressed Concrete Beam (NU35+1)	2,469	lf
Falsework Inspection	1	LS
Bridge Deck Grooving	1,710	sy
Bridge Handrail (Metal)(1'-10")	358	lf
Bridge Handrail (Metal)(3'-6")	353	lf
Bridge Handrail (Metal)(4'-6")	353	lf
Bridge Drainage System	1	LS
Electrical Lighting System	1	LS
Concr Sidewalk 6" (Reinf)	607	sf
Aesthetic Metal Tower (Set Price)	1	LS
LUMP SUM BID ITEMS - LANDSCAPING		
Sodding	1	LS
MEASURED QTY BID ITEMS - LANDSCAPING		
Tree Rem, Large	1	ea
Tree Rem, Small	2	ea
LUMP SUM BID ITEMS - TRAFFIC		
Pvmt Markings	1	LS
Signing	1	LS
Traffic Signalization	1	LS
Traffic Control	1	LS
MEASURED QTY BID ITEMS - TRAFFIC		
AC Sidewalk, Temp	295	sf
Signing, Elec. Port. Message (ea per dy)	100	day
LUMP SUM BID ITEMS - RETAINING WALL		
Concr (Grade 4.0) (AE)	108	cy
Reinf Steel (Grade 60)(Epoxy Coated)	31,020	lb
Excavation (Class III)	654	cy
Handrail (Metal)(3'-6")	48	lf
Handrail (Metal)(4'-6")	51	lf
Piles (Steel Sheet)	88	lf
MEASURED QTY BID ITEMS - DRAINAGE		
Pipe, SWS 24" (RCP)	87	lf
Pipe, SWS 30" (RCP)	41	lf
Pipe, SWS 54" (RCP)	78	lf
MH, Reinf Concr	2	ea
MH, Standard SWS (5')	1	ea
Fill, Sand (Flushed & Vibrated)	43	lf
Rip-Rap, Light Stone (18")	841	sy
Rip-Rap Rem & Reset	69	sy
Rip-Rap Rem	578	sy
Concr (Grade 4.0)(AE)	23	cy
Reinf Steel (Grade 60)(Epoxy Coated)	2,433	lb
MEASURED QTY BID ITEMS - EROSION CONTROL BMPS		
BMP, Back of Curb Protection	53	lf

BMP, Construction Entrance	2	ea
BMP, Silt Fence	1,510	lf

All bids received will thereafter be publicly opened, read aloud and considered by the Board of Bids and Contracts. All work to be done under the direction and supervision of the City Manager and according to plans and specifications on file in the office of the City Engineer. Bidders will be required to enclose a bid bond in the amount of five percent (5%) with each as a guarantee of good faith. The Wichita City Council reserves the right to reject any and all bids.

Dated at Wichita, Kansas, October 2, 2019.

Karen Sublett, City Clerk

This information and any addenda is also available on the City's Web Page at:
<https://ep.wichita.gov/>.