

TO BE PUBLISHED ONE TIME ON OCTOBER 2, 2019

SEALED PROPOSALS

Notice is hereby given that bids will be received at the office of the Purchasing Manager, up to 10:00 a.m., Friday, October 18, 2019 for the following project:

**2nd St Bridge & Douglas Ave Bridge at Brookside**

472-85435\_472-85436

**LUMP SUM BID ITEMS - 2nd St Paving (715739)**

Field Office and Lab (Type A)	1	LS
Mobilization	1	LS
Rem of Existing Structures	1	LS
Transport of Salvaged Materials	1	LS
Site Clearing	1	LS
Site Restoration	1	LS
Crushed Rock Base 7", Reinf	492	sy

**LUMP SUM BID ITEMS - 2nd St Bridge (715739)**

Pipe. SWS, RCBC (3-12' x 5')	54	lf
Handrail	126	lf

**LUMP SUM BID ITEMS - 2nd St Roadside Improv. (715739)**

Sodding, Buffalo	1	LS
------------------	---	----

**LUMP SUM BID ITEMS - 2nd St Traffic (715739)**

Traffic Control	1	LS
-----------------	---	----

**MEASURED QTY BID ITEMS - 2nd St Paving (715739)**

Pvmt &/or Curb Rem	465	sy
Sidewalk, Drive, &/or Pkg Lot Rem	93	sy
Concr Pvmt 8" (Reinf)	413	sy
Concr C & G, Type 1 (6" & 1-1/2")	187	lf
Concr Curb, Mono Edge (6" & 1-1/2")	49	lf
Concr Curb, Mono Edge, Rem & Repl	40	lf
Concr Sidewalk 4"	958	sf
WCR w/Det Warn	4	ea
Pipe Rem	50	ea
Pipe, Cut & Cap	2	ea

**MEASURED QTY BID ITEMS - 2nd St SWS (715739)**

Inlet, Curb (Type 1, Special)(L=10' W=3')	6	ea
Inlet, Curb (Type 1)(L=10' W=3')	3	ea
Inlet Hookup	9	ea
Pipe, SWS, RCP 18"	60	lf
Pipe, SWS, HERCP (14"x23"){18}	29	lf
Pipe, SWS, RCP 24"	43	lf
Pipe, SWS, PVC 4", Perforated	100	lf
MH, Shallow SWS (4')	1	ea

**MEASURED QTY BID ITEMS - 2nd St Erosion Control (715739)**

BMP, Back of Curb Protection	205	lf
------------------------------	-----	----

BMP, Construction Entrance	2	ea
BMP, Curb Inlet Protection	9	ea
BMP, Silt Fence	231	lf
BMP, Silt Fence Removal	231	lf
<b>MEASURED QTY BID ITEMS - 2nd St Roadside Improv. (715739)</b>		
Riprap, Light Stone	389	sy
<b>MEASURED QTY BID ITEMS - 2nd St Traffic (715739)</b>		
Signing, Elec. Portable Message (ea per dy)	40	dy
<b>LUMP SUM BID ITEMS - Douglas Ave Paving (715740)</b>		
Field Office & Lab (Type A)	1	LS
Mobilization	1	LS
Rem of Existing Structures	1	LS
Transport of Salvaged Materials	1	LS
Site Clearing	1	LS
Site Restoration	1	LS
Crushed Rock Base 8", Reinf	524	sy
<b>LUMP SUM BID ITEMS - Douglas Ave Bridge (715740)</b>		
Pipe, SWS, RCBC (3-12' x 5')	80	lf
Handrail	126	lf
<b>LUMP SUM BID ITEMS - Douglas Ave Roadside Improv. (715740)</b>		
Sodding, Buffalo	1	LS
<b>LUMP SUM BID ITEMS - Douglas Ave Traffic (715740)</b>		
Pvmt Markings	1	LS
Traffic Control	1	LS
<b>MEASURED QTY BID ITEMS - Douglas Ave Paving (715740)</b>		
Pvmt &/or Curb Rem	502	sy
Sidewalk, Drive, &/or Pkg Lot Rem	211	sy
AC Pvmt 7" (5" Bit Base)	446	sy
Concr C&G, Type 1 (6" & 1-1/2")	222	lf
Concr C&G Rem & Repl	52	lf
Concr Curb, Mono Edge, Rem & Repl	53	lf
Concr Sidewalk 4"	2,059	sf
WCRw/ Det Warn	4	ea
Pipe, Rem	149	lf
Pipe, Cut & Cap	2	ea
Inlets Rem	1	ea
<b>MEASURED QTY BID ITEMS - Douglas Ave SWS (715740)</b>		
Inlet, Curb (Type 1, Special)(L=10' W=3')	6	ea
Inlet, Curb (Type 1,)(L=15' W=4')	1	ea
Inlet Hookup	7	ea
Pipe, SWS, 24" RCP	43	lf
Pipe, SWS 4" PVC, Perforated	60	lf
Fill, Sand (Flushed and Vibrated)	43	lf
<b>MEASURED QTY BID ITEMS - Douglas Ave Erosion Control (715740)</b>		
BMP, Back of Curb Protection	354	lf
BMP, Construction Entrance	2	ea
BMP, Curb Inlet Protection	7	ea
BMP, Silt Fence	268	lf

BMP, Silt Fence Rem 268 lf  
**MEASURED QTY BID ITEMS - Douglas Ave Roadside Improv. (715740)**

Riprap, Light Stone 631 sy

**MEASURED QTY BID ITEMS - Douglas Ave Traffic (715740)**

Concr Safety Barrier, Temp 200 lf

Signing, Elec. Portable Message (ea per dy) 80 dy

AC Pvmt 6", Temp 368 sy

AC Curb, Temp 391 lf

**MEASURED QTY BID ITEMS - 2nd St SS Improv. (628108)**

Pipe, SS 15" 168 lf

Pipe, Casing (24"ID Min.) 50 lf

MH, Standard SS (5'), Lined 1 ea

MH, Standard SS (5') Doghouse, Lined 1 ea

MH, Bench & Invert, Rem & Repl 2 ea

MH, Line Existing 2 ea

MH, Plug Existing 2 ea

MH, Connect to Existing 1 ea

MH, Joint Wrap 76 lf

MH Frame and Cover, Repl 2 ea

Air Testing, SS Pipe 165 lf

Pipe, Abandon In Place 90 lf

Fill, Flowable 36 lf

**MEASURED QTY BID ITEMS - Douglas Ave SS Improv. (628108)**

MH, Rehab 1 ea

MH Adj w/o New Ring & Cover 1 ea

MH Adj w/ New Ring & Cover 1 ea

**Add Alternate #1**

**MEASURED QTY BID ITEMS - 2nd St SWS (715739)**

Concr Pvmt Rem & Repl 31 lf

Inlet, Curb (Type 1)(L=10' W=3') 1 ea

Inlet Hookup 1 ea

Pipe, SWS, RCP 18" 36 lf

Pipe, SWS, PVC 4", Perforated 20 lf

Fill, Sand (Flushed & Vibrated) 36 lf

BMP, Curb Inlet Protection 1 ea

All bids received will thereafter be publicly opened, read aloud and considered by the Board of Bids and Contracts. All work to be done under the direction and supervision of the City Manager and according to plans and specifications on file in the office of the City Engineer. Bidders will be required to enclose a bid bond in the amount of five per cent (5%) with each as a guarantee of good faith. The Wichita City Council reserves the right to reject any and all bids.

Dated at Wichita, Kansas, September 26, 2019.

Karen Sublett, City Clerk

This information and any addenda is also available on the City's Web Page at:

<http://ep.wichita.gov/>.