

**City of Wichita, Kansas
Americans with Disabilities Act Transition Plan**

Fire Station 15

7923 E. Lincoln

August 2005



Prepared by

DMCG

Disability Management Consulting Group L.L.C.

2801 Jonquil Place

Columbia, MO 65202

In conjunction with

The Great Plains ADA & IT Center and the City of Wichita Disability Advisory Board

City of Wichita – ADA/504 Transition Plan – Fire Station #15 - August 2005 Legend: **Blue** font identifies hyperlinked documents – **Red** font indicates recommended changes to structures or policies

Locations	Structural Inconsistencies		Recommended Corrections/Modifications to Ensure Program Access			Criteria – L=low, M=medium, H=high			Supplemental Technical Information			Finalized Actions		
Location	Identified Issue	ADAAG Specifications	Recommended Correction			Priority (overall)	Public Access	Frequency - PWD	Photo #	Conceptual Costs	Support Information	Finalized Correction	Date to be Corrected	Date Completed (Include initial)
1. Public Restroom	Round knobs exist on the lavatory for faucet controls.	4.19	Round knobs exist on the lavatories. At least one lavatory should have faucet controls that do not require a tight grasp or pinching or twisting of the wrist to operate. Replace the round knobs with lever type, push button or motion activation faucet controls.			L	L	M	1	\$100	See Attachment 4 – Lavatory Specifications for more information on accessible lavatories.	THIS FIRE STATION IS RECOMMENDED TO BE CLOSED TO MEMBERS OF PUBLIC, AS IT IS <i>TECHNICALLY INFEASIBLE</i> TO MAKE ANY MEANINGFUL STRUCTURAL ADJUSTMENTS TO IT, IN ORDER TO MAKE IT ADAAG COMPLIANT.	N/A	N/A (cmk)
2. Public Restroom	The mirror is located too high at 49-inches.	4.19.6	At least one mirror in each restroom is required to be located so that the bottom edge of the reflecting surface is a maximum height of 40-inches. Typically, this barrier can be removed by installing an additional full length mirror. Install a full length mirror.			L	L	M	1	\$25	ADAAG			
3. Public Restroom	The toilet stall is totally inaccessible due to numerous barriers.	4.23	Inconsistencies include, but are not limited to, very narrow stall, lack of grab bars, toilet seat too low, toilet paper dispenser wrong location, etc. Modify the restroom to comply with ADAAG specifications, if it is technically feasible to do so.			L	L	M	2	\$3,000	Restroom Figures – Building Blocks			

Fire Station #15 - Conceptual Cost Projections

Total	\$3,125
Year Three (Low)	\$3,125
Year Five (Medium)	\$0
Year Ten (High)	\$0